

15-165-20365-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 9 - 1970
12-9-70
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Martin Explorations Et al
Complete Address 527 UNION CENTER
Wichita, Kansas 67202
Lease Name Pirner Well No. 1
Location 150' NE of C SW NE Sec. 19 Twp. 19 Rge. (E) (W) 20
County Rush Total Depth 3930'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Sage Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 6 P Day 7 Month 12 Year 1970

The above well was plugged as follows:

RTD 3930' 8 5/8 csg set at 332' cwc 200 sk. Cmt. Mat. 100 sk reg poz w/6% gel.
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 12/9/70
INV. NO. 3031-W