

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 17 1972  
3-17-72  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name George E. Reed

Complete Address 1223 Union National Bldg., Wichita, Kansas 67202

Lease Name Frank Well No. I

Location C SW NW Sec. 4 Twp. 19 Rge. (E) (W) 20

County Rush Total Depth 4285'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A

Other well as hereafter indicated (NONE) Washdown

Plugging Contractor Santa Fe Pipe & Supply, Inc.

Address Box 562 Great Bend, Kansas 67530 License No. 574

Operation Completed: Hour 12 M Day 15 Month 3 Year 1972

The above well was plugged as follows:

Total Depth 4285' 8 5/8 csg set at 334' cwc Cmt. Mat. 50-50 poz cmt W/4% added gel.

4 1/2 csg sett at 4284' cw 200 sk cmt.

4 1/2 csg Perf. (4174-4177)

Filled 4 1/2 csg W/sd (4160-4285) Dumped 4 sk cmt W/dump bailer. (4125-4160)

Cutoff and recovered 2500' of 4 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water W/300 lbs hulls, released 8 5/8 plug

and pumped 70 sk cmt, displaced with 13 bbl water, capped with 20 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Messing  
Well Plugging Supervisor

INVOICED

DATE 3-17-72

INV. NO. 5369-W