

15-165-20463-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1973
6-4-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Beardmore Oil, Inc.

Complete Address 700 One Twenty Bldg., Wichita, Kansas

Lease Name Pivonka Well No. 1

Location SE SE SW Sec. 4 Twp. 19 Rge. (E) (W) 20

County Rush Total Depth 4226'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XXX

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Oil

Address Wichita, Kansas License No.

Operation Completed: Hour 3:30 P Day 2 Month 6 Year 1973

The above well was plugged as follows:

RTD 4226' 8 5/8 csg set at 355' cwc Cmt. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 50 sk

cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 25 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Lio J. Massey
Well Plugging Supervisor

INVOICED

DATE 6/4/73

INV. NO. 9453-W