

KANSAS

4

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
12-17-71
DEC 17 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Okmar Oil Company & Walters Drilling
Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas
Lease Name Frank "A" Well No. 1
Location C NW SW Sec. 4 Twp. 19 Rge. (E) (W) 20
County Rush Total Depth 4333'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Rains & Williamson
Address Wichita, Kansas License No.
Operation Completed: Hour 6 A Day 14 Month 12 Year 1971

The above well was plugged as follows:

RTD 4333' 8 5/8 csg set at 253' cwc Cmt. Mat. 50-50 poz W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Geo A. Mason*
Well Plugging Supervisor

DATE 12/17/71
INV. NO. 4828-W