

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENCY'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1978
1-24-78
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 165-20,613-0008 (of this well)

Operator's Full Name Rains & Williamson Oil, Inc.

Complete Address 435 Page Ct., 220 W. Douglas, Wichita, Kansas 67202

Lease Name Brack "A" Well No. 1

Location 100' N W/2 SW SE Sec. 4 Twp. 19 Rge. (E) (W) 20

County Rush Total Depth 4243'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by Sun Cementing Co.

Address License No. 685

Operation Completed: Hour 1:15 P Day 20 Month 1 Year 1978

The above well was plugged as follows:

Total Depth 4243' 8 5/8 csg set 404' cwc 250 sk.

4 1/2 csg set 4241' cw 125 sk cem.

Set 4 1/2 csg "Perm. Plug" at 3800' Cutoff & recovered 2750' of 4 1/2 csg.

Sun Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/200 lbs

hulls -followed with 80 sk 50-50 poz 6% -displaced with 7 sk gel & water & capped

with 20 sk 50-50 poz 6% & shutin. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 1-26-78

INV. NO. 6645-W