

KANSAS STATE CORPORATION COMMISSION

RECEIVED STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

AUG 23 1960 8-23-60 CONSERVATION DIVISION Wichita, Kansas

TO: Jewel M. Ogden, Director 500 Insurance Building 212 North Market Wichita 2, Kansas

File No. _____ County: Rush

Location: NE SW NW Sec. 10 Twp. 19 Rge. 20 (E) (W)

Name of Field: _____ Total Depth: 4343

I have this date completed supervision of plugging of:

Lease Name: Yost Well No. 1

Operator's Full Name: Natural Gas & Oil Co

Complete Address: Box 105 Great Bend, Kans

Plugging Contractor: Forbes Casing Pulling Co

Address: Great Bend, Kans License No. 49

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 1PM Day 13 Month 8 Year 60

The above well was plugged as follows:

8 5/8" 509' circulated with cement - 5 1/2" 4342' with 100 sax cement, perf 4210'.

Filled with sand to 4200', set 4 sax cement with dump bailer, pulled 3642' 5 1/2" to 840', circulated hole with heavy mud through 5 1/2" at 840' (30 sax gel), displaced 20 sax cement through 5 1/2" at 520', heavy mud to 180', displaced 20 sax cement through 5 1/2" at 180', heavy mud to 40', set rock and cement to bottom cellar.

Mudding and cementing by Forbes Co pump truck.

Signed: [Signature] Conservation Division Agent

Reviewed: [Signature] Field Supervisor

Remarks:

INVOICED DATE 8/26/60 INV. NO. 1816-W