

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -165 -20,565 - 0000 (of this well)

6-18-76

Operator's Full Name Rains & Williamson Oil Co., Inc.
Complete Address 435 Page Court, 220 W. Douglas, Wichita, Kansas
Lease Name Yost "A" Well No. 1
Location 150' SE of NE SW NW Sec. 10 Twp. 19 Rge. (E) (W) 20
County Rush Total Depth 4240'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 3:15 P Day 17 Month 6 Year 1976

The above well was plugged as follows:

RTD 4240' 8 5/8 csg set 402' cwc Plg. Mat. 50-50 poz 2% total gel.
Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.
Heavy mud to 300' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Red Mandy
Well Plugging Supervisor

DATE 6/21/76
INV. NO. 3368-W