

15-165-02002-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3-17-69
MAR 17 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mobil Oil Company

Complete Address: P. O. Box 1070 Great Bend, Kansas 67530

Lease Name Eva Webs "A" Well No. 1

Location SW SW SW Sec. 10 Twp. 19 Rge. 20 (E) (W) XX

County Rush Total Depth 4300'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 12N Day 16 Month 3 Year 1969

The Above well was plugged as follows:

Total Depth 4300' 8 5/8 csg set at 195' CWC

5 1/2 csg set at 4299' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (4200-4300) Dumped 5 sk cmt W/dump bailer. (4160-4200)

Cutoff and recovered 2500' of 5 1/2 csg

Pumped thru 8 5/8 plug container with 25 sk gel W/5 sk hulls, plug and 130 sk 50-50 poz
cmt. W/6% total gel. Max. pres. 500 lbs. SI pres 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/17/69

INV. NO. 9490-11

Signed: Geo F. [Signature]
Well Plugging Supervisor