

CP3

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 19-36

LOCATION SW-SW-SE

SEC. 16 TWP. 18 RGE. 18-W

Dry Hole Abandoned Oil Well X Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 1 Lease Nicks

Operator Great Lakes Carbon Corp. Address 301 Peter Bldg - Wichita - Kans.

Field County Rush

Total Depth 3852 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 1234 ft. Circulated With Cement.
5 1/2" casing set at 3838 ft. Plugged back to 3820 ft
with chat - Dumped 5 sacks of cement at 3820 ft
Pipped off & pulled the 5 1/2" casing - mud to 240 ft
Set Rock Bridge & 15 sacks of cement at 240 ft
Mud to 35 ft - Bridge & 10 sacks of cement
at the surface.

Re S. Pipe Pulling Co - Plugging Contractors

PLUGGING
FILE SEC. 16 T 18 R 180
BOOK PAGE 19 LINE 36

SEP 9 X 1950
9-9-50
STATE CORPORATION
COMMISSION

C. H. Stough
District Conservation Agent

Date 9-8-50