

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 10 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Hicks of L.J. Dreiling & Sons has this
date requested permission to plug the following described well:

Mr. Hicks guarantees payment of the plugging fee.

Operator's full Name: H. B. Mabee Co.

Complete Address: Box 94718 Oklahoma City, Okla.

Lease Name: Becker Well No. 1

Location: NW NE NE Sec. 33 Twp. 19 Rge. (E)(W) 19

County: Rush Total Depth 4275 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Hicks was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 660' and displace

70 sk cmt thru drill pipe. Heavy mud to 360' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar. Plug rat hole with

2 sk cmt.

Very truly yours,

L. J. Massing
Conservation Division Agent