

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission  
CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 5 1967  
6-5-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Williamson of Vaughan Drlg Co. has this  
date requested permission to plug the following described well:

Mr. Williamson guarantees payment of the plugging fee.

Operator's full Name: Mull Drlg. Co. Inc.,

Complete Address: 1625 Wichita Plaza Wichita, Kansas

Lease Name: Maresch Well No. 1

Location: SW NW Sec. 32 Twp. 19 Rge. 19 (E)(W) X

County Rush Total Depth 4290 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Williamson was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace  
25 sc cement thru drill pipe. Heavy mud to 270' set cementing plug and  
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole with  
2 sc cement.

Very truly yours,

Leo F. Massey  
Conservation Division Agent