



15-203-00032-0000

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 28 1964
 9-28-64
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Clyde Merckle of Lauck Drilling Co., Inc. has this
 date requested permission to plug the following described well:
Cleary Petroleum, Inc.,
 Mr. Merckle guarantees payment of the plugging fee.

Operator's full Name: Cleary Petroleum, Incorporated,

Complete Address: 310 Kermac Building, Oklahoma City, Oklahoma.

Lease Name: Kunkel Well No. 1

Location: NE-SE Sec. 27 Twp. 20 Rge. (E) (W) 35

County Wichita Total Depth 5120 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Merckle was instructed to plug the well as follows:

294'--8 5/8" Surface pipe, cement circulated with 225 Sx.

Circulate hole with heavy mud, set plug @ 550' and 20 Sx. cement.

" " 280' and 20 Sx. cement.

" " 40' with 1/2 sk hulls & 10 Sx. cement.

Very truly yours,

H. A. Nichols
 Conservation Division Agent