

State of Kansas



20002
15-203-~~0000~~0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
SEP 5 1967
9-5-67
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Pfannenstiel of Leben Drlg. Co. has this
date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: Leben Drlg. Inc. etal

Complete Address: 815 Wichita Plaza Wichita, Kansas

Lease Name: Hester Well No. 1

Location: C SW SE Sec. 11 Twp. 20 Rge. 35 (E)(W) X

County Wichita Total Depth 5090 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pfannenstiel was instructed to plug the well as follows:

Gun pits, circulate heavy mua, set cementing plug at 1980' and displace

100 sc cement thru drill pipe. Heavy mud to 420' set cementing plug and

displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing plug,

1/2 sc hulls and 10 sc cement to base of cellar. Plug rathole with 2 sc

cement.

Very truly yours,

Leo J. Massey
Conservation Division Agent