



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

OCT 28 1964

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Payne of Flint Engineering and Const. Co.
has this

date requested permission to plug the following described well:

Mr. Payne guarantees payment of the plugging fee.

Operator's full Name: Bichus Oil Company

Complete Address: 721 East Central, Wichita, KANSAS

Lease Name: Titus A Well No. #1

Location: W2-W2-SW Sec. 21 Twp. 31 Rge. 7 (E) (W) X

County Hann Total Depth 471.7 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Payne was instructed to plug the well as follows:

258 feet of 8 5/8 inch surface pipe circulated with cement.
4709 feet of 5 1/2 feet long string perforated at 4336 sand to
4300 feet cemented with 5 sacks. Hole filled to 250 feet with mud
10 foot rock bridge, cemented with 25 sacks. Hole filled to
40 feet with mud. 10 foot rock bridge and 10 sacks cement to
base of collar.

Very truly yours,

Conservation Division Agent