

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 12 1968

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. H. J. Pankratz of H-30 Drilling Inc. has this date requested permission to plug the following described well:

Mr. Pankratz guarantees payment of the plugging fee.

Operator's full Name: Jayhawk Oil Co.

Complete Address: 412 One-Twenty Bldg., Wichita, Kansas

Lease Name: Titus Well No. # 1

Location: W/2 W/2 SW/4 Sec. 21 Twp. 31 Rge. 7 (E) (W) W

County Harper Total Depth 4710 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pankratz was instructed to plug the well as follows:

256' of 8 5/8" surface pipe, cemented with 225 sacks.

Fill hole with drilling mud to 240', 1st cementing plug,

1/2 sack hulls, cement with 20 sacks. Fill hole with drill-

mud to 40', 2nd cementing plug, 1/4 sack hulls, cement with

10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent