

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

RECEIVED
 STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

JAN 29 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Jan. 24, 1963.

Dear Sir:

Mr. D. B. Pully of Forbes Caseing Pulling Co. has this date requested permission to plug the following described well:

Mr. D. B. Pully guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Co.

Complete Address: Box 267 Great Bend, Kansas.

Lease Name: Titus #1 Well No. Titus #1

Location: SW-SW-SW Sec. 21 Twp. 31 Rge. 7 (E) (W)

County Harper County Total Depth 4750' ^{Abandoned} Oil Well &

Abandoned Gas Well Input Well SWD Well D & A Lost Hole

Mr. D. B. Pully was instructed to plug the well as follows:

~~4749' of 5½" long string cemented with 250 sacks cement. plugged back to 4725'. Top perforation at 4702'. Sanded to 4690' and 5 sacks cement. 3042' of 5½" pipe pulled. 254' of 8 5/8" surface pipe circulated with cement. Hole filled to 200' with mud, 10' rock bridge & 20 sacks cement. Hole filled to 40' with mud, 10' rock bridge, & 10 sacks cement to base of cellar.~~

Very truly yours,

Herman J. Rustus
 Conservation Division Agent