

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-203-20,128-000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR A.L. Abercrombie, Inc. KCC LICENSE # 5393  
(owner/company name) (operator's)  
ADDRESS 150 N. Main, Suite #801 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 262-1841

LEASE Uhland WELL# 3 SEC. 25 T. 20S R. 35 (East West)

NW - NE - SPOT LOCATION/OOOO COUNTY Wichita

660' FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

1980' FEET (in exact footage) FROM (E/W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 287.17' CEMENTED WITH 225 SACKS

PRODUCTION CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: \_\_\_\_\_

ELEVATION 3145'/3150' T.D. 4975 PBDT \_\_\_\_\_ ANHYDRITE DEPTH 2265  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING 1st plug at 2280' with 50 sks, 2nd plug at 1150' with 80 sks, 3rd plug at 650' with 40 sks, 4th plug at 310' with 55 sks, 5th plug at 40'

with 10 sks, 155 sks in rat hole. Total 250 sks 60/40 pos, 6% gel, 1/4# floseal per sk.  
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ IS ACO-1 FILED? Enclosed

If not explain why? \_\_\_\_\_ N/A

**PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.**

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Walter Brown PHONE# (316) 855-7063

ADDRESS P.O. Box 1139 City/State Cimarron, KS 67835

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30684  
(company name) (contractor's)

ADDRESS 150 N. Maine, #801, Wichita, KS 67202 PHONE # (316) 262-1841

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 09-17-97 at 9:15 p.m.

**PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT**

DATE: 10/7/97 AUTHORIZED OPERATOR/AGENT: Steve Frankly  
(signature)