

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File **ONE** Copy)

API # 15-203-20,120,0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Abercrombie Drilling, Inc. KCC LICENSE # 5422  
(owner/company name) (operator's)

ADDRESS 150 N. Main, Suite 801 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 262-1841

LEASE BRACK WELL# 1 SEC. 25 T. 20S R. 35 (East/West)

NW - E/2 - SE - NW SPOT LOCATION/0000 COUNTY Wichita

2040' FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

2240' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 262.00' CEMENTED WITH 175 SACKS

PRODUCTION CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: \_\_\_\_\_

ELEVATION 3147'/3152' T.D. 5063' PBDT \_\_\_\_\_ ANHYDRITE DEPTH 2254'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill in hole with heavy mud. 1st plug at 2275'-50 sks, 2nd plug at 2150'-80 sks, 3rd plug at 690'-40 sks, 4th plug at 290'-40 sks, 5th plug at 40'-10 sks, rathole 15 sks.

Total 235 sks 60/40 pos, 6% gel, 1/4# Floseal per sk.  
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ IS ACO-1 FILED? Enclosed

If not explain why? \_\_\_\_\_

**PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.**

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Gary Fisher PHONE# (316) 872-2038

ADDRESS 909 Church St. City/State Scott City, KS. 67871

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30684  
(company name) (contractor's)

ADDRESS 150 N. Main, Suite 801 Wichita, Ks. 67202 PHONE # (316) 262-1841

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 5:30 p.m. on 6-7-95

**PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT**

DATE: 6-23-95 AUTHORIZED OPERATOR/AGENT: Jack K. Wharton  
(signature)