

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 1 1966
 9-1-66
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Rowe of Slawson Drlg. Co. has this
 date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson

Complete Address: 408 One Twenty Bldg., Wichita, Kansas

Lease Name: Thalheim "A" Well No. 1

Location: C SW NE Sec. 1 Twp. 19 Rge. 20 (E)(W) X

County Rush Total Depth 4105' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 480'

and displace 30 sc cement thru drill pipe. Heavy mud to 290' set

cementing plug and displace 20 sc cement thru drill pipe. Heavy

mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to

base of celler. Plug rat hole with 2 sc cement.

Very truly yours,

Geo. Massey
 Conservation Division Agent