

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 9 - 1970
12-8-70
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Shawn of Sage Drlg. has this date requested permission to plug the following described well:

Mr. Shawn guarantees payment of the plugging fee.

Operator's full Name: Martin Explorations Et al

Complete Address: Wichita, Ks.

Lease Name: Pirner Well No. 1

Location: 150' NE of C SW NE Sec. 19 Twp. 19 Rge. (E)(W) 20

County: Rush Total Depth 3930' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Shawn was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 660' and displace
70 sk cmt thru drill pipe. Heavy mud to 300' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug,
1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. F. Massey
Conservation Division Agent