

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Roberts of Leben Mfg Co. has this date requested permission to plug the following described well:

Mr. Roberts guarantees payment of the plugging fee.

Operator's full Name: Leben Mfg + Bankoff

Complete Address: 486 1/2 Blvd Kans.

Lease Name: Schlegel Well No. 1

Location: Ne-Ne-Nw Sec. 7 Twp. 19 Rge. 20 (E)(W)

County Rush Total Depth 4377 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Roberts was instructed to plug the well as follows:

**Jett pits circulate hole with heavy mud, set cementing plug at 540 ft.,
and displace 50 sac cement thru drill pipe, heavy mud to 210 ft.,
set cementing plug and displace 50 sac cement, heavy mud to 40 ft.,
set cementing plug, 1/4 sac hulls and 10 sac cement, cementing to base of
cellar.**

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours, Gilbert P. Leiker
CONSERVATION DIVISION
Wichita, Kansas Conservation Division Agent

DEC - 2 1965
12-2-65