

CP2

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 12 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Buchheister of John O. Farmer, Inc. has this

date requested permission to plug the following described well:

Mr. Buchheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Inc.

Complete Address: 370 W. Wichita Ave. Russell, Ks.

Lease Name: Webbs Well No. 1

Location: C NE SW Sec. 10 Twp. 19 Rge. (E)(W) 20

County: Rush Total Depth 4256 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Buchheister was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace

70 sk cmt thru drill pipe. Heavy mud to 180' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Massey
Conservation Division Agent