

AFFIDAVIT AND COMPLETION FORM


ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one (Oil, gas, dry, SWD, OWWO, injection). Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR Beren Corporation API NO. 15-101-20,573-0000
 ADDRESS 970 Fourth Financial Center COUNTY Lane
Wichita, KS 67202 FIELD ALAMOTA CNW
 **CONTACT PERSON Evan Mayhew LEASE WEISER
 PHONE (316) 265-3311

PURCHASER Central Crude Corporation WELL NO. 1
 ADDRESS 402 Commerce Plaza WELL LOCATION NE NW SE
Wichita, Kansas 67202 Ft. from _____ Line and
 _____ Ft. from _____ Line of
 the 9 SEC. 18S TWP. 27W RGE.

DRILLING CONTRACTOR Abercrombie Drilling, Inc.
 ADDRESS 801 Union Center
Wichita, KS 67202



WELL PLAT
 (Quarter) or (Full) Section - Please indicate.

PLUGGING CONTRACTOR _____
 ADDRESS _____
 TOTAL DEPTH 4601' PBD 4590
 SPUD DATE 11/09/81 DATE COMPLETED 11/21/81
 ELEV: GR 2651 DF KB 2656

KCC
 KGS

DRILLED WITH (~~W~~) (ROTARY) (~~W~~) TOOLS
 Report of all strings set — surface, intermediate, production, etc. (New) / (~~Used~~) casing.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	20#	327.01'	60-40 pos.	225	2% gel, 3% c.c.
PRODUCTION	7-7/8"	4 1/2"	10.5#	4600'	60-40 pozmix	200	2% gel, 10% salt

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	DPJS	4542-4549
TUBING RECORD					
Size	Setting depth	Pecker set at			
2-3/8"	4590	----			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated
500 gallons 15% acid	4542 - 4549

TEST DATE: 2/3/82 PRODUCTION 24 BOPD, no water
 Date of first production 2/1/82 Producing method (flowing, pumping, gas lift, etc.) Pumping A.P.I. Gravity NA till sales
 RATE OF PRODUCTION PER 24 HOURS Oil 24 Gas -0- Water 0 % Gas-oil ratio ---- CFPB
 Disposition of gas (vented, used on lease or sold) _____ Producing interval (s) Cherokee Sand

** The person who can be reached by phone regarding any questions concerning this information.
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

RECEIVED
 FEB 10 1982
 2-10-82
 CONSERVATION DIVISION
 Wichita, Kansas

Name of lowest fresh water producing stratum UNKNOWN Depth _____
 Estimated height of cement behind pipe Cement did circulate to surface.

WELL LOG

Shew all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Sand & Shale	0	332		
Sand & Shale	332	2033		
Anhydrite	2033	2064		
Shale & Red Beds	2064	2317		
Sand & Shale	2317	3055		
Shale & Shells	3055	3551		
Sand & Shale	3551	3786		
Shale & Lime	3786	4383		
Lime & Shale	4383	4495		
Shale & Lime	4495	4601		
Rotary Total Depth		4601		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

A F F I D A V I T

STATE OF KANSAS, COUNTY OF SEDGWICK SS,

DON W. BEAUCHAMP OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS GEOLOGIST FOR BEREN CORPORATION OPERATOR OF THE WEISER LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 1st DAY OF FEBRUARY 19 82, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(s) *Don W. Beauchamp*
 SUBSCRIBED AND SWORN TO BEFORE ME THIS 9th DAY OF FEBRUARY 19 82



Karen G. Berry
 NOTARY PUBLIC

MY COMMISSION EXPIRES: November 4, 1984