


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barber County. Sec. 26 Twp. 30 Rge. 11 (W)
Location as "NE/CNWSWK" or footage from lines NE NE NE
Lease Owner Aylward Drilling Company et al
Lease Name Wehling Well No. 1
Office Address 813 1st Natl. Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed February 19 1957
Application for plugging filed February 19 1957
Application for plugging approved February 19 1957
Plugging commenced February 19 1957
Plugging completed February 19 1957
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives - Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4817 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	230'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from 4817' to 225'; Halliburton plug, 1/3 sack of hulls and 25 sacks of cement from 225' to 165'; heavy mud from 165' to 35'; Halliburton plug at 35' with 1/3 sack of hulls and 10 sacks of cement from 35' to surface. (cement was mixed in a barrel and poured down the surface casing).

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Aylward Drilling Company
Address 813 1st Natl. Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Paul W. Hesse (employee of owner) or (individual) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse
813 1st Natl. Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of February, 1957

My commission expires December 11, 1957

Duane Jessup
Notary Public.

PLUGGING
FILE SEC. 26 T. 30 R. 11 W
BOOK PAGE 142 LINE 8

RECEIVED
STATE CORPORATION COMMISSION
02-23-1957
FEB 23 1957
CONSERVATION DIVISION
Wichita, Kansas

15-007-00398-00-00

WEHLING #1

Casing Record:

8 5/8" - 230'

Company: Aylward Drilling Company
Contractor: Aylward Drilling Company

Commenced: February 4, 1957
Completed: February 18, 1957

Location: NE NE NE
Section 26-30-11W
Barber County
Kansas
Elev. 1793 D.F.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand	0	110	Set 8 5/8" surf. pipe @ 230' w/200 sx.
Redbed	110	230	
Redbed and shale	230	850	Geological Tops:
Salt	850	1150	Heebner 3677
Shale & shells	1150	1556	Douglas Shale 3748
Shale & Lime shelves	1556	1780	Douglas Sand 3804
Lime & shale	1780	1810	Brown Lime 3861
Shale	1810	1945	Lansing/K.C. 3876
Shale & lime	1945	2116	B/Kansas City 4258
Lime with shale	2116	2235	Mississippian 4426
Lime & shale	2235	2420	Viola 4688
Lime with shale	2420	2552	Simpson 4766
Lime & shale	2552	2715	T.D. 4817
Shale & lime	2715	3045	
Shale with some lime	3045	3180	DST 4114-45 Open 1 hr. Rec. 50' muddy S.W. IFP 26 $\frac{7}{8}$ ", FFP 55 $\frac{7}{8}$ "; IBHP 1422 $\frac{7}{8}$ "/20" FBHP 1208 $\frac{7}{8}$ "/20"
Lime & shale	3180	3480	
Sand	3480	3630	
Sand & shale	3630	3720	
Sand & lime	3720	3758	
Lime & shale	3758	3802	DST 4417-35 Open 1 hr. Rec. 16' mud with spots of oil. IFP 26 $\frac{7}{8}$ ", BFP 37 $\frac{7}{8}$ "; IBHP 488 $\frac{7}{8}$ "/20" - FBHP 70 $\frac{7}{8}$ "/20"
Sand	3802	3890	
Lime & shale	3890	3935	
Lime	3935	4005	
Lime & shale	4005	4051	DST 4417-60 Open 1 hr. Rec. 45' mud with specks off oil. IFP 37 $\frac{7}{8}$ ", FFP 45 $\frac{7}{8}$ "; IBHP 168 $\frac{7}{8}$ "/20" - FBHP 75 $\frac{7}{8}$ "/20"
Lime	4051	4120	
Lime & shale	4120	4145	
Lime	4145	4200	
Lime with shale	4200	4295	
Lime & shale	4295	4370	
Lime	4370	4431	
Miss. Chat	4431	4435	
Chat	4435	4460	
Lime	4460	4493	
Shale	4493	4519	
Shale & lime	4519	4615	
Shale with lime	4615	4708	
Lime & shale	4708	4731	
Lime	4731	4817 T.D.	D. & A.

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W Hesse
Paul W. Hesse

Subscribed and sworn to before me this 21st day of February, 1957.

Duane Jessup
Notary Public

My commission expires December 11, 1957

PLUGGING
FILE SEC 26 T. 30 R. 11W
BOOK PAGE 14.2 LINE 8

RECORDED
STATE COMMISSION
02-23-1957