

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-165-21,142-0000

LEASE NAME Keener

TYPE OR PRINT

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

WELL NUMBER 3

SPOT LOCATION NE NE SW

LEASE OPERATOR J.A. Allison

SEC. 22 TWP. 18 RGE. 18 (E) OR (W)

ADDRESS 300 W. Douglas, Suite 305
Wichita, Kansas 67202

COUNTY Rush

PHONE # (316) 263-2241 OPERATORS LICENSE NO. 5027

DATE WELL COMPLETED 11-7-83

CHARACTER OF WELL D&A
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

PLUGGING COMMENCED 11-7-83

PLUGGING COMPLETED 11-7-83

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Belpre, KS

Is ACO-1 FILED? Yes IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM _____ T.D. 3916'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1169'	

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

50 sx. @ 1200', 25 sx. @ 600', 10 Sx. @ 40', 10 sx. in Rathole, 10 sx. in Mousehole

105 sx. 60/40 Poz-mix, 2% Gel, 3% CC, plug down @ 3:00 AM, 11-7-83
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Allied Cementing Co., Inc. LICENSE No. _____
ADDRESS P.O. Box 678, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, SS.

K.T. Woodman (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) K.T. Woodman
(ADDRESS) 1022 Union Center, Wichita, KS

SUBSCRIBED AND SWORN TO BEFORE ME THIS 9th DAY OF November, 1983

Kathryn A. Voigt
NOTARY PUBLIC

MY COMMISSION EXPIRES: April 20, 1985 Kathryn A. Voigt

RECEIVED
STATE CORPORATION COMMISSION
NOV 10 1983
11-10-83
CONSERVATION DIVISION
Wichita, Kansas

KATHRYN A. VOIGT
NOTARY PUBLIC
STATE OF KANSAS
My Appt Expires 4-20-85

RECEIVED
STATE CORPORATION COMMISSION
NOV 11 1983
CONS. DIVISION
WICHITA, KANSAS

FORM CP-4
REVISED 06-83

K. T. WOODMAN
 RES. PHONE 733-0418
 OFF. PHONE 265-7650
 WICHITA, KANSAS

D. J. IANNITTI
 PHONE 792-2921
 GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY
Rotary Drilling Contractors

1022 UNION CENTER
 150 N. MAIN
 WICHITA, KANSAS 67202

November 9, 1983

Company:	J.A. Allison
Farm:	Keener #3
Location:	NE NE SW
Section:	22-18-18W
County:	Rush
Contractor:	Woodman & Iannitti Drilling Company
Total Depth:	3916'
Comm:	November 1, 1983
Comp:	November 7, 1983
Casing:	8-5/8" 24# set @ 1176' w/450 sx. 60/40 Poz-mix, 3% CC, 2% Gel

Figures Indicate Bottom Formations:

30	Top Soil
45	Post Rock
190	Shale & Clay
250	Sand
547	Shale
830	Dakota Sand
1163	Shale, Red Bed
1176	Anhydrite
1201	Anhydrite
1380	Shale & Shells
1991	Shale
2325	Shale & Lime
2605	Shale & Lime
2915	Shale & Lime
3170	Lime
3410	Lime
3550	Lime
3690	Lime
3770	Lime
3790	Lime
3916	Arbuckle

I certify the above to be a true and correct copy of the Drillers Log to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING COMPANY

K. T. Woodman

K.T. Woodman, Partner

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 10 1983
 CONSERVATION DIVISION
 Wichita, Kansas