


15-165-00031-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rush County. Sec. 22 Twp. 18 Rge. 18 (E) 18 (W)
Location as "NE/CNW/SW" or footage from lines NE NW SW
Lease Owner Musgrove Petroleum Corporation
Lease Name DIRKS Well No. 1
Office Address 518 Petroleum Building, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed April 14, 19 53
Application for plugging filed September 27, 19 54
Application for plugging approved September 28, 19 54
Plugging commenced October 9, 19 54
Plugging completed October 9, 19 54
Reason for abandonment of well or producing formation Dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production September 30, 1954
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3790 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	958	
				5-1/2"	3788	2661'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 3792' to 3780'.
Dumped 5 sacks cement from 3780' to 3740'.
Pumped 10 sx mud and 100 sx cement down the hole.

10-16-54
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jayhawk Casing Pulling Company,
Address Russell, Kansas.


STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
518 Petroleum Building, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of October 19 54

Anna E. Ross
Notary Public.

My commission expires July 16, 1955.



CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corp. & Rupp-Ferguson Oil Co.
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: Dirks # 1
 LOCATION: NE NW SW Section 22-18-18
 Rush County, Kansas

COMMENCED: March 30, 1953
 COMPLETED: April 14, 1953

0	30	Clay
30	118	Shale and shells
118	130	Sand
130	180	Shale and shells
180	210	Sand and shale
210	310	Shale
310	433	Shale and shells
433	445	Sand and pyrite
445	525	Shale and shells
525	760	Sand and shells
760	959	Sand, shale, shells and red bed
959	1158	Shale and shells
1158	1180	Anhydrite
1180	1369	Shale
1369	1915	Shale and shells
1915	2211	Lime and shale
2211	3355	Lime and shale
3355	3690	Lime
3690	3769	Cherty lime
3769	3785	Conglomerate
3785	3790	Arbuckle
	3790	Rotary Total Depth

Set 8 5/8" at 958' with 450 sacks of cement.
 Set 5 1/2" casing at 3788' with 150 sacks of cement.

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the Dirks # 1, S¹c. 22-18-18, Rush County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By Gordon L. Koelling
 Secretary-Treasurer

Subscribed and sworn to before me a Notary Public in and for the Sedgwick County, Kansas, this 17, 1953.

Mary S. Dunn
 Notary Public

My Commission Expires: November 14, 1956.

PLUCCING
 TWTI SEC 22 T 18 R 18W
 BOOK PAGE 106 LINE 41

RECEIVED
 STATE RECORDS DEPARTMENT
 SEP 28 1954
 9-28-54