

15-165-01822-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Rush County. Sec. 22 Twp. 18 Rge. 18 (W)

Location as "NE/CNW&SW" or footage from lines C-NW-NW-NW

Lease Owner SUNRAY OIL CORPORATION

Lease Name Anna Hoffman Well No. 1

Office Address Box 195, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 26 19 53

Application for plugging filed January 26 19 53

Application for plugging approved January 27 19 53

Plugging commenced January 26 19 53

Plugging completed January 26 19 53

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3876 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing-KC	Dry	3448		8 5/8	982	None
Arbuckle	Dry	3825	3876			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed Howco plug to 300 feet. Displaced 35 sax Pozmix cement on top of plug. Pushed top plug to 35 feet. Ran 13 sax Pozmix cement on plug.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Company

Address Philtower Building, Tulsa, Oklahoma

STATE OF KANSAS, COUNTY OF BARTON, ss.

W. E. Westbrook, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. E. Westbrook, Jr.

Box 195, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of February, 19 53

My commission expires December 24, 1956

Notary Public.

PLUGGING
FILE SEC-227-18-R-18
BOOK PAGE 75 LINE 2

RECEIVED
STATE CORPORATION COMMISSION
FEB 4 - 1953
2-4-53
CONSERVATION DIVISION

Sunray Oil Corporation
Tulsa, Oklahoma

Tulsa, Oklahoma
January 30, 1953

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: January 9, 1953
Drilling Completed: January 26, 1953

Anna Hoffman #1 NW-
NW-NW-Sec. 22-18S-18W
Rush County, Kansas.

DRILLERS LOG


Post Rock & Surface Clay	0-189
Shale & Hard Shells	189-380
Shale & Shells	380-590
Dakota Sand	590-810
Red Bed	810-860
Shale & Shells	860-980
Red Bed	980-1180
Anhydrite	1180-1225
Shale & Shells	1225-1940
Lime & Shale	1940-2120
Lime	2120-2305
Hard Sand & Chert	2305-2395
Lime & Shale	2395-2460
Shale & Lime	2460-2530
Lime & Shale	2530-2980
Shale & Lime	2980-3100
Lime	3100-3250
Lime & Shale	3250-3335
Lime	3335-3724
Lime & Chert	3724-3760
Chert	3760-3770
Shale	3770-3780
Lime & Shale	3780-3792
Conglomerate	3792-3800
Lime Chert	3800-3829
Arbuckle	3829-3876 TD

I, Frank E. Stickle, hereby certify the above to be a true and complete drillers log of Sunray Oil Corporation's Anna Hoffman #1 NW-NW-NW-Section 22-18S-18W, Rush County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Benham
Notary Public

February 13, 1956
My Commission Expires



STATE COURT
2-4-53
FILED
COMMISSIONER