

To: 1 110011
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,933 - 0800

C SE NE, SEC. 34, T 20 S, R 22 W
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Cure Well # 1-34

Operator: Gear Petroleum Co., Inc.

County Ness 143.00

Name:

Address 300 Sutton Place

Well Total Depth 4400 Mississippi feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 498

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Co. License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 9:45 pm Day: 3 Month: October Year: 19 85

Plugging proposal received from Bruce Fickle

(company name) Red Tiger (phone) 316-263-2371

Elevation 2170 GL

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1425'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 700' with 80 sx cement

3rd plug at 500' with 40 sx cement

4th plug at 250' with 30 sx cement

solid bridge

5th plug hulls - plug at 40' Plugging Proposal Received by James R. Kapp

cement to surface with 10 sx cement

(TECHNICIAN)

7th plug to circulate rat hole with 10 sx cement

Plugging Operations attended by Agent: All Part None X

Operations Completed: Hour: 11:00 pm Day: 3 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1440' with 50 sx cement, 2nd plug at 1030' with 80
sx cement, 3rd plug at 530' with 50 sx cement, 4th plug at 250' with 30 sx cement,

5th & 6th plug - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement,

7th plug to circulate rat hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging
STATE CORPORATION COMMISSION

DATE 10-15-85

INV. NO. 10570

10-3

OCT 10 1985
10-10-85
CONSERVATION DIVISION

Signed

James R. Kapp
(TECHNICIAN)

FORM CP-2/3
Rev. 01-84