

1 060041

10-5

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,507-0000

NE NE SW, SEC. 36, T 20 S, R 22 W/E

1980 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5316

Lease Name Shank Well # 1

Operator: Falcon Exploration Inc.

County Ness 144.30

Name & Address 125 N. Market, Suite 1075

Well Total Depth 4440 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 748

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Blue Goose Drilling Company License Number 5104

Address P.O. Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 6 p.m. Day: 5 Month: 10 Year: 19 90

Plugging proposal received from Martin Miller

(company name) Blue Goose Drilling Company (phone) 316-793-6031

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1336-1372'

1st plug at 1380' with 50 sx cement, 2nd plug at 780' with 50 sx cement,

3rd plug at 300' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9 p.m. Day: 5 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1380' with 50 sx cement,

2nd plug at 780' with 50 sx cement,

3rd plug at 300' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
OCT 19 1990
10-19-90
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(Buyer/Client) observe this plugging.

DATE 10-29-90

Signed Case Morris
(TECHNICIAN)

DIV. NO. 29752

EFFECTIVE DATE: 9-29-90

FORM MUST BE TYPED
FORM C-1 4/90

State of Kansas

135-23,507-0000

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 9 27 90
month day year

NE NE SW Sec 36 Twp 20 S, Rg 22 East West

OPERATOR: License # 5316
Name: Falcon Exploration Inc.
Address: 125 N. Market, Suite 1075
City/State/Zip: Wichita, KS 67202
Contact Person: Jim Thatcher
Phone: (316) 265-3351

1980 feet from South line of Section
2970 feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License # 5104
Name: Blue Goose Drilling Co.

County: Neos
Lease Name: Shank Well #: 1
Field Name: Wildcat
Is this a Prorated Field? yes no
Target Formation(s): Mississippi
Nearest lease or unit boundary: 660'
Ground Surface Elevation: unknown feet MSL
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no
Depth to bottom of fresh water: 100
Depth to bottom of usable water: 650
Surface Pipe by Alternate: 1 2
Length of Surface Pipe Planned to be set: 700
Length of Conductor pipe required: none
Projected Total Depth: 4350
Formation at Total Depth: Mississippi
Water Source for Drilling Operations:
... well ... farm pond other

Well Drilled For: Well Class: Type Equipment:
 Oil ... Inj ... Infield Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... G.W.C. ... Disposal Wildcat ... Cable
... Seismic; ... # of Holes

If G.W.C.: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? yes no
If yes, total depth location: _____

DER Permit #: _____
Will Cores Be Taken?: yes no
If yes, proposed zone: _____

Exp. 3/24/91

AFFIDAVIT

670' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Martin Miller INIT. RM

SPUD DATE 9-25-90

LENGTH SURFACE PLANNED 700' ±

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE _____
SURFACE PIPE 8 1/2" @ 748 CONDUCTOR _____
ANHYDRITE T- 1236 B- 1322 ELEVATION _____

TD 4440 FORMATION _____

RAN PIPE @	DV TOOL	ALT II	DONE
		SX	Y N
Arbuckle Plug @		Ft. W/	SX
Hug./Council @		Ft. W/	SX
Anhydrite Base @	<u>1380</u>	Ft. W/	<u>50</u> SX
1/2 Base Anyh. @	<u>780</u>	Ft. W/	<u>50</u> SX
1/2, 1/2 Plug @	<u>300</u>	Ft. W/	<u>40</u> SX
Bottom Surface @		Ft. W/	SX
40' Plug @	<u>10</u>	Ft. W/	<u>10</u> SX

RAT HOLE CIRC/W 0.5 SX MOUSE HOLE W/ _____ SX

WATER WELL _____ SX (Dir. Well Pond Hauling)

TECHNICIAN DATE 9-29-90

TYPE OF CEMENT 6040 670

STARTING TIME 6:00 (AM/PM) DATE 10-5

COMPLETION TIME 9:00 (AM/PM) DATE 10-5

CEMENT COMPANY Allied