

1 030591

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-21,498-0000 *R*

C NW NE, SEC. 33, T 20 S, R 22 *W/EX*

4620 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Dean-Barricklow Well # 1

Operator: Gear Petroleum Co., Inc.

County Ness 141.57

Name & Address 300 Sutton Place

Well Total Depth 4356 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 463 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Gear Petroleum Co., Inc. License Number 5151

Address 300 Sutton Place, Wichita, KS 67202

Company to plug at: Hour: 10:45 am Day: 27 Month: November Year: 1985

Plugging proposal received from Dan Hoberecht

(company name) Gear (phone) 316-265-3351

were: Stage collar at 1413' with 230 sx 5 1/2" at 4350' PBD 4242' Perfs at 4336-38'
Cement circulated from 1413' to surface
CIBP at 4342

Squeeze well with 2 sx hulls, 25 sx cement, 20-30 sx gel, release 8 5/8" rubber plug and pump
135 sx cement.

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)
Dan Goodrow observed all

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 am Day: 27 Month: November Year: 1985

ACTUAL PLUGGING REPORT 1st plug CIBP at 4342', 2nd plug squeezed well with 2 sx hulls,
25 sx cement, 27 sx gel, 1 sack hulls and 135 sx cement.

Maximum pressure 1000 psi and shut in 200 psi

Remarks: No recovery. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

Dan Goodrow observed the plugging

RECEIVED

(I did not observe this plug) STATE CORPORATION COMMISSION

Signed Steve Durrant (TECHNICIAN)

INVOICED

DATE DEC 10 1985

DEC 5 1985

INV. NO. 11360

CONSERVATION DIVISION
Wichita, Kansas