

1 090381

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-20,953-0000
C SE NE, SEC. 33, T 20 S, R 22 W/EX

TECHNICIAN'S PLUGGING REPORT

3300 feet from S section line
660 feet from E section line

Operator License # 6455

Lease Name Dean Well # 1

Operator: Apache Drilling Co., Inc.

County Ness

Name & Address P.O. Box 454

Well Total Depth 4345 141.21 feet

Ness City, KS 67560

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 438

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Apache Drilling Co., Inc. License Number 6455

Address P.O. Box 454, Ness City, KS 67560

Company to plug at: Hour: 2 p.m. Day: 21 Month: 12 Year: 19 93

Plugging proposal received from Clint Base

(company name) Apache Drilling Co., Inc. (phone) 913-798-3995

vers: 5 1/2" at 4336' w/275 sx cement, 9' open hole, DV tool at 1410' w/325 sx cement

1st plug sand back to 4300' and dump 5 sx cement on top of sand through bailer,

2nd plug circulate cement through tubing from 1400-0'.

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1993
12-23-93
CONSERVATION DIVISION
Wichita, Kansas
Steve Durrant

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:20 p.m. Day: 22 Month: 12 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 5 sx cement on top of sand

through bailer,

Perforated 5 1/2" casing at 730', tried to pump into perms-would not take 1000# pressure.

2nd plug ran tubing to 1450', circulated to surface with 100 sx cement.

Backside has cement, cannot pump into. Backside circulated from 1450' to surface.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

~~INVOICED~~ observe this plugging.

Signed [Signature]
(TECHNICIAN)

DATE DEC 29 1993

INV. NO. 39571

12-22 FEB 23 1994