

1070518

2-24-88

API NUMBER 15-165-21,403-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SW SW, SEC. 13, T 19 S, R 20 W/E
990 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3532

Lease Name Nelson Well # 1-13

Operator: CMX, Inc.
Name & Address 1026 Union Center Building
Wichita, KS 67202

County Rush 139.75
Well Total Depth 4300 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 11:05 a.m. Day: 24 Month: 2 Year: 1988

Plugging proposal received from Tony Martin

(company name) Abercrombie Drilling (phone) 913-743-5443
Elevation 2147'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1375-1405'
1st plug at 1400' with 50 sx cement, 2nd plug at 700' with 60 sx cement,
3rd plug at 390' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:15 p.m. Day: 24 Month: 2 Year: 1988

ACTUAL PLUGGING REPORT 1st plug at 1400' with 50 sx cement,
2nd plug at 700' with 60 sx cement,
3rd plug at 390' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

3-4-88

Observe this plugging.

INVOICED

Signed Dan Johnson
(TECHNICIAN)

DATE 3-4-88

INV. NO. 20010

2-24

NOTICE OF INTENTION TO DRILL

Expected Spud Date... February 17, 1988 (see rules on reverse side) month day year
 API Number 16-166-21403-0000 2
 OPERATOR: License # 03532 NE. SW. SW. Sec. 13, Twp. 19. S, Rg. 20... X East
 Name CMX, Inc. 990 Ft. from South Line of Section
 Address 1026 Union Center Building 4290 Ft. from East Line of Section
 City/State/Zip Wichita, Kansas 67202
 Contact Person DAUG McGinness II
 Phone 316-269-9052
 (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5422 Nearest lease or unit boundary line 990 feet
 Name Abercrombie Drilling Inc. County Bush
 City/State Wichita, Kansas Lease Name Nelson Well # 1-13
 Well Drilled For: Well Class: Type Equipments: Ground surface elevation 2147 feet MSL
 Oil Storage Infield Mud Rotary Domestic well within 330 feet: yes no
 Gas Inj Pool Ext. Air Rotary Municipal well within one mile: yes no
 OWWO Expl Wildcat Cable Depth to bottom of fresh water 300
 Depth to bottom of usable water 600
 Surface pipe by Alternate: 1 X
 Surface pipe planned to be set 320
 Conductor pipe required None
 Projected Total Depth 4350 feet
 Formation Mississippian

If OWWO: old well info as follows:
 Operator _____
 Well Name _____
 Comp Date _____ Old Total Depth _____
 I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
 Date 02-12-88 Signature of Operator or Agent _____ Title President

For KCC Use:
 Conductor Pipe Required _____ feet; Minimum Surface Pipe Required 320 feet per Alt. X
 This Authorization Expires 8-12-88 Approved By [Signature] 2-12-88

2-17-88 EFFECTIVE DATE: 2-17-88
8 3/8 - 350
no WW

NE. SW. SW. Sec. 13, Twp. 19. S, Rg. 20... X East
 West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep. <u>Base Anhydrit</u>	or formation with <u>50</u>	feet of <u>60-40 Poz</u>
2nd plug @ ft. deep <u>720</u>	or formation with <u>50</u>	feet of <u>60-40 Poz</u>
3rd plug @ ft. deep <u>370</u>	or formation with <u>40</u>	feet of <u>60-40 Poz</u>
4th plug @ ft. deep <u>40</u>	or formation with <u>10</u>	feet of <u>60-40 Poz</u>
5th plug @ ft. deep _____	or formation with _____	feet of _____

(2) Rathole to surface minus 5 feet (b) Mousehole to surface minus 5 feet

<u>CMX inc</u>	<u>SX</u>
<u>Tony Martin</u>	<u>SX</u>
<u>Nelson 1-13</u>	<u>SX</u>
<u>359-878</u>	<u>SX</u>
<u>1375-1405-anhy</u>	<u>SX</u>
<u>197</u>	<u>SX</u>
<u>1400 w/ 50SX</u>	<u>SX</u>
<u>500 w/ 60SX</u>	<u>SX</u>
<u>390 w/ 40SX</u>	<u>SX</u>
<u>40 w/ 10SX</u>	<u>SX</u>
<u>15 rathole</u>	<u>SX</u>
<u>60/40 6 page</u>	<u>SX</u>
<u>Allied</u>	<u>SX</u>
<u>EMUSE RULE CIRCULAR W/</u>	<u>SX</u>
<u>WATER WELL PLUGGED W/</u>	<u>SX</u>
<u>CEMENT COMPANY</u>	<u>SX</u>
<u>TECHNICIAN</u>	<u>SX</u>

3-4-88