

1 090901

2-22

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-203-20,132-0000  
NW SE, SEC. 30, T 20 S, R 35 W/E  
1980 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422

Lease Name McMichaels Well # 1

Operator: Abercrombie Drilling, Inc.

County Wichita 168.68

Name & Address 150 N. Main, Ste. 801

Well Total Depth 5190 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 318

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie RTD, Inc. License Number 30684

Address 150 N. Main, Ste. 801, Wichita, KS 67202

Company to plug at: Hour: 7 p.m. Day: 22 Month: 2 Year: 19 98

Plugging proposal received from Tony

(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

Work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2306' with 50 sx cement, 2nd plug at 1100' with 80 sx cement,

3rd plug at 700' with 40 sx cement, 4th plug at 340' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:30 p.m. Day: 22 Month: 2 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug at 2306' with 50 sx cement,

2nd plug at 1100' with 80 sx cement,

3rd plug at 700' with 40 sx cement,

4th plug at 340' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

FEB 25-1998  
2-25-98  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

Additional description is necessary, use BACK of this form.

I (XXX) did not observe this plugging.

DATE FEB 26 1998

WV. NO. 50153

2-22

Signed [Signature] (TECHNICIAN)