

Td: 1070043
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202
11-25

API NUMBER 15- 203-20,129 - 0000

E/2 NE SE, SEC. 26, T 20 S, R 35 W/E
1980 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 31093
Operator: Becker Oil Corporation
Name & Address: 122 E. Grand, Ste. 212
Ponca City, OK 74601

Lease Name Brack Well # 1
County Wichita 165.75
Well Total Depth 5100 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 297

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382
Address P.O. Box 916, Garden City, KS 67846

Company to plug at: Hour: 9:30 p.m. Day: 24 Month: 11 Year: 1997

Plugging proposal received from Phil Lloyd
(company name) Cheyenne Drilling, Inc. (phone) 316-277-2062

Work: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 2300' with 50 sx cement, 2nd plug at 1150' with 80 sx cement,
3rd plug at 650' with 40 sx cement, 4th plug at 330' with 40 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Scott Alberg (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10 a.m. Day: 25 Month: 11 Year: 1997

ACTUAL PLUGGING REPORT 1st plug at 2250' with 50 sx cement,
2nd plug at 1150' with 80 sx cement, 3rd plug at 650' with 40 sx cement,
4th plug at 330' with 40 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. (Additional description is necessary, use BACK of this form.)

INVOICED
DATE 12-8-97
INV. NO. 49595

12-2-97
Signed [Signature] (TECHNICIAN)