

To: **1051843**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-30

API NUMBER 15-203-20,117-0000  
SW NE, SEC. 26, T. 20 S, R. 35 W/X  
1980 feet from N& section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422  
Operator: Abercrombie Drilling, Inc.  
Name & Address: 150 N. Main, Ste. 801  
Wichita, KS 67202

Lease Name Titus Well # 1  
County Wichita  
Well Total Depth 5080 165.10 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 287

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
NEVER PRODUCED

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Leon's Drilling Service License Number 30044

Address P.O. Box 163, Plainville, KS 67663

Company to plug at: Hour: 10 a.m. Day: 30 Month: 9 Year: 19 94

Plugging proposal received from Eddy Abercrombie

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

logs: 4 1/2" at 4616' w/175 sx cement, CIBP 4500', Perfs at 4520-21, 4429-33'

1st plug sand back to 4380' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 25 sx cement at cutoff, 3rd plug at 2260' with 50 sx cement,

4th plug at 1200' with 80 sx cement, 5th plug at 600' with 50 sx cement,

6th plug at 320' with 50 sx cement, 7th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6:30 p.m. Day: 30 Month: 9 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4380' and dumped 4 sx cement on top of sand through bailer, Gel spacers between plugs:

2nd plug at 2660' with 25 sx cement, 3rd plug at 2260' with 50 sx cement,

4th plug at 1200' with 80 sx cement,

5th plug at 600' with 50 sx cement,

6th plug at 320' with 50 sx cement, 7th plug at 40' with 10 sx cement,

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2865' of 4 1/2" casing.

Additional description is necessary, use BACK of this form.)  
observe this plugging.

**INVOICED**

DATE OCT 06 1994

WV. NO. 41310

Signed Richard W. Lacy  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
10-4-94  
OCT 04 1994  
CONSERVATION DIVISION  
WICHITA, KANSAS