

Tax: 1 090852  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

9-17

API NUMBER 15- 203-20,128-0000

NW NE, SEC. 25, T. 20 S, R. 35 W/X  
660 feet from NXX section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Uhland Well # 3

Operator: A.L. Abercrombie, Inc.

County Wichita 161.69

Name & Address 150 N. Main, Ste. 801

Well Total Depth 4975 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 286

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie RTD, Inc. License Number 30684

Address 150 N. Main, Ste. 801, Wichita, KS 67202

Company to plug at: Hour: 6 p.m. Day: 17 Month: 9 Year: 19 97

Plugging proposal received from Walter Brown

(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

Work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2280' with 50 sx cement, 2nd plug at 1150' with 80 sx cement,

3rd plug at 650' with 40 sx cement, 4th plug at 310' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9:15 p.m. Day: 17 Month: 9 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 2280' with 50 sx cement,

2nd plug at 1150' with 80 sx cement,

3rd plug at 650' with 40 sx cement,

4th plug at 310' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE SEP 25 1997

INV. NO. 49130

Signed [Signature] (TECHNICIAN)

9-24-97