

To: 1031331 6-8
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 203-20,120-0000

E/2 SE NW, SEC. 25, T 20 S, R 35 W/E
2040 feet from ~~N~~ section line
2240 feet from ~~W~~ section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5422
Operator: Abercrombie Drilling, Inc.
Name & Address: 150 N. Main, Ste. 801
Wichita, KS 67202

Lease Name Brack Well # 1
County Wichita
Well Total Depth 5060 164.45 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 262

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie RTD, Inc. License Number 30684

Address 150 N. Main, Ste. 801, Wichita, KS 67202

Company to plug at: Hour: 3:15 p.m. Day: 8 Month: 6 Year: 1995

Plugging proposal received from Gary Fisher

(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2257-75'

1st plug at 2275' with 50 sx cement, 2nd plug at 1250' with 80 sx cement,
3rd plug at 690' with 40 sx cement, 4th plug at 290' with 40 sx cement,
5th plug at 40-0' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 6:15 p.m. Day: 8 Month: 6 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 2275' with 50 sx cement,
2nd plug at 1250' with 80 sx cement, 3rd plug at 690' with 40 sx cement,
4th plug at 290' with 40 sx cement,
5th plug at 40-0' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 6-14-95
INV. NO. 42963
6-8

Signed Steve Durrant (TECHNICIAN)