

1 060244

8-10

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-203-20,114-0000

N/2 NW SE, SEC. 25, T. 20 S, R. 35 W XX
2310 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Uhland Well # 2

Operator: A.L. Abercrombie, Inc.

County Wichita

Name & Address 150 N. Main, Ste. 801

Well Total Depth 5050 164.13 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 283

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie RTD, Inc. License Number 30684

Address 150 N. Main, Ste. 801, Wichita, KS 67202

Company to plug at: Hour: 1:30 p.m. Day: 10 Month: 8 Year: 1994

Plugging proposal received from Tony Martin

(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2250-64'

1st plug at 2800' with 100 sx cement, 2nd plug at 2300' with 50 sx cement,

3rd plug at 1250' with 60 sx cement, 4th plug at 650' with 50 sx cement,

5th plug at 320' with 50 sx cement, 6th plug at 40' with 10 sx cement,

7th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 6 p.m. Day: 10 Month: 8 Year: 1994

ACTUAL PLUGGING REPORT 1st plug at 2800' with 100 sx cement,

2nd plug at 2300' with 50 sx cement,

3rd plug at 1250' with 60 sx cement,

4th plug at 650' with 50 sx cement,

5th plug at 320' with 50 sx cement, 6th plug at 40' with 10 sx cement,

7th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(If additional description is necessary, use BACK of this report.)

observe this plugging.

INVOICED

DATE AUG 29 1994

INV. NO. 11044

Signed Case Morris (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1994

CONSERVATION DIVISION
WICHITA, KANSAS