

3-8 210K

To: 1 120538
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 203-20,095-0000
C NE NE, SEC. 23, T 20 S, R 35 W/E
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5005

Lease Name Buerkle "E" Well # 1
County Wichita 164.94

Operator: Sunburst Exploration Company, Inc.
Name & Address 125 N. Emporia, Suite 112
Wichita, KS 67202

Well Total Depth ~~5125~~ 5075 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 220

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling License Number 5422
Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 2:30 p.m. Day: 8 Month: 3 Year: 19 91

Plugging proposal received from Wayne Shively
(company name) Abercrombie Drilling (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2232-45'
Elevation 2095'
1st plug at 2250' with 50 sx cement, 2nd plug at 1125' with 50 sx cement,
3rd plug at 575' with 50 sx cement, 4th plug at 240' with 50 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 7:15 p.m. Day: 8 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2250' with 50 sx cement,
2nd plug at 1125' with 50 sx cement,
3rd plug at 575' with 50 sx cement,
4th plug at 240' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by B.J. Titan.
(if additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

DATE 4-3-91
INV. NO. 31318

STATE CORPORATION COMMISSION
5-15-91
MAR 15 1991

Signed Duane Rankin (TECHNICIAN)