

1091024

TO: STATE CORPORATION COMMISSION

API NUMBER 15-203-20,133-0000
200'S SW SE SEC. 19, T 20 S, R 35 W

CONSERVATION DIVISION - PLUGGING SECTION 460 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME GLEE SMITH WELL # 1-19

TECHNICIAN'S PLUGGING REPORT

COUNTY WICHITA 164.13

OPERATOR LICENSE # 32457

WELL TOTAL DEPTH 5050 FEET

OPERATOR: ABERCROMBIE ENERGY, LLC

PRODUCTION CSG: SIZE " FEET

NAME AND 150 N MAIN, SUITE 801

SURFACE CASING: SIZE 8 5/8" @ 332' WITH SX

ADDRESS WICHITA, KS 67202

CONDUCTOR CSG: SIZE " @ '

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ABERCROMBIE RTD LICENSE NUMBER 30684

ADDRESS 150 N MAIN, STE 801, WICHITA, KS 67202-1383

COMPANY TO PLUG AT: HOUR: 12:00 AM DAY: 11 MONTH: 11 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM GARY FISHER

(COMPANY NAME) ABERCROMBIE RTD (PHONE) 316-262-1841

WERE:

1ST PLUG AT 2330' WITH 50 SX CEMENT. 2ND PLUG AT 1100' WITH 80 SX CEMENT.

3RD PLUG AT 600' WITH 40 SX CEMENT. 4TH PLUG AT 360' WITH 50 SX CEMENT.

5TH PLUG AT 40' WITH 10 SX CEMENT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

NO MOUSE HOLE.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 3:00 AM DAY: 11 MONTH: 11 YEAR: 1999

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 2330' WITH 50 SX CEMENT. 2ND PLUG AT 1100' WITH 80 SX CEMENT.

3RD PLUG AT 600' WITH 40 SX CEMENT. 4TH PLUG AT 360' WITH 50 SX CEMENT.

5TH PLUG AT 40' WITH 10 SX CEMENT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

NO MOUSE HOLE.

REMARKS: USED 60/40 POZMIX 1/2 GEL 1/4 FLO SEAL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

DATE 12/13

INV. NO. 60884

SIGNED (TECHNICIAN)

FORM CP-2/3

CONSERVATION DIVISION
WICHITA, Kansas

11-29-99