

To: 1 080165
STATE CORPORATION COMMISSION

API NUMBER 15- 203-20,130-0000

Wichita State Office Bldg. - PLUGGING SECTION

S/2 NW SW, SEC. 11, T 20 S, R 35 W/2

130 S. Market, Room 2078

Wichita, KS 67202

12-3

1650 feet from S section line

660 feet from W2 section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 31093

Lease Name Warrington Well # 1

Operator: Becker Oil Corporation

County Wichita 164.94

Name & Address 122 E. Grand, Ste. 212

Well Total Depth 5075 feet

Ponca City, OK 74601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382

Address P.O. Box 916, Garden City, KS 67846

Company to plug at: Hour: 9:30 a.m. Day: 3 Month: 12 Year: 19 97

Plugging proposal received from Phil Lloyd

(company name) Cheyenne Drilling, Inc. (phone) 316-277-2062

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2285'

1st plug at 2280' with 50 sx cement, 2nd plug at 1170' with 80 sx cement,

3rd plug at 690' with 30 sx cement, 4th plug at 300' with 40 sx cement,

5th plug at 40-0' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 3 Month: 12 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 2280' with 50 sx cement,

2nd plug at 1170' with 80 sx cement,

3rd plug at 690' with 30 sx cement, 4th plug at 300' with 40 sx cement,

5th plug at 40-0' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (Stamp) Reserve this plugging.

Signed Kevin D. Shuck (TECHNICIAN) [Signature]

DATE 49680

INV. NO. 49680