

TECH# 1060106 API Number 15 203200020001

TECHNICIANS PLUGGING REPORT

Sec 11 T 20 R 35 (W)

4-21

660 Feet from S Sect Line
1980 Feet from E Sect Line

OPERATOR

LICENSE# 31093 Lease Name Hester Well # 1

Operator: Becker Oil Corp. County Wichita 164.45

Name & Clyde M Becker Well Total Depth 5060 Feet

Address 212 E Grand #212 Production Pipe: Size 4 1/2 Feet 4707

Ponca City, OK. 74601 Conductor Pipe: Size _____ Feet _____

Surface Casing: Size 8 5/8 Feet 450

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereinafter indicated _____

Plugging Contractor Post and Mastin Well Service License # 8438

Address P.O. Box 297 Garden City, Ks. 67846

Company to plug at: Hour 11:00 am Day 21 Month 04 Year 98

Plugging Proposal received from: Doug Brown

(company name) Becker Oil Company (phone) 316-287-4724

were: Set cast iron bridge plug above perms. with 4 sxs of cement. Then cement as pipe is pulled.

4-23-98

PLUGGING PROPOSAL RECEIVED BY Michael Maier
(Technician)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour 4:00pm Day 21 Month 04 Year 98

ACTUAL PLUGGING REPORT Cast iron bridge plug was set at 4375' with 4sxs cement on top of bridge plug.

1st plug at 1973' w/ 50sxs cement

2nd plug at 1160' w/ 80sxs cement

3rd plug at 470' w/ 50sxs cement

4th plug at 40' w/ 10sxs cement

Remarks: Allied Cementing did cement job. Used 60/40 6% gel. Pulled 3388' of 4 1/2" casing

I **DID** / **DID NOT** observe this plugging
(circle one)

Signed Michael Maier
(Technician)

INVOICED

DATE MAY 04 1998

INV. NO. 50420