

1 120473

9-28

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
210 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19- 165-20,958-00-00
50' W
SW SE SW, SEC. 12, T 16 S, R 17 W/E
330 feet from S section line
3680 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6242
Operator: Julius A. Legleiter
Name & Address: 505 E. 20th
Hays, KS 67601

Lease Name Herrman Well # A-1
County Rush 116.35
Well Total Depth 3580 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 920

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10:30 a.m. Day: 28 Month: 9 Year: 19 90

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 3578' w/150 sx cement, PBT 3438', Perfs at 3310-20', DV 815-0'
1st plug pump in 4 1/2" casing with 200 lbs. hulls and 150 sx cement,
2nd plug pump in 8 5/8" with 50 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:45 a.m. Day: 28 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped into 4 1/2" casing with 200 lbs. hulls and 200 sx cement. Pumping pressure 0-600 psi and shut in 200 psi.

Pumped in 4 1/2" X 8 5/8" annulus with 5 gal water at 600#. Shut in 600#.

RECEIVED STATE CORPORATION COMMISSION

OCT 4 1990 10-04-1990

Remarks: Used 60/40 Pozmix 8% gel by B.J. Services. No casing recovery. Wichita, Kansas
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-10-90
INV. NO. 29616
9-28

Signed Duane Rankin (TECHNICIAN)