

To: 1 120474  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-28 21269  
API NUMBER 19- 165-21,169-00-00  
NE NE NW, SEC. 12, T 16 S, R 17 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 6242

4950 feet from S section line

2970 feet from E section line

Operator: Julius A. Legleiter

Lease Name Herrman Well # 2

Name & Address 505 E. 20th

County Rush 117.13

Hays, KS 67601

Well Total Depth 3604 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1099

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 28 Month: 9 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 3604' w/250 sx cement, PBT 3208', Top of perms 3075'.

1st plug sand back to 2970' and dump 4 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 200 lbs. hulls, and 150 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 a.m. Day: 28 Month: 9 Year: 1990

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 2970' with 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 2 sx gel, 50 sx cement, 10 sx gel, 200 lbs. hulls and 150 sx cement.

Pumping pressure 0-1150 psi and shut in 550 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2000' of 4" casing  
(if additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
10-04-1990  
OCT 4 1990

INVOICED

DATE 10-10-90

INV. NO. 29615

9-28

Signed Duane Rankin (TECHNICIAN)