

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-20937-00-01
Spot: W2E2NENE Sec/Twnshp/Rge: 33-20S-22W
660 feet from N Section Line, 510 feet from E Section Line
Lease/Unit Name: BARRICKLOW Well Number: 2
County: NESS Total Vertical Depth: 4381 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 447 WITH 250 SX CMT
Production: Size 5.5 feet: 4380 WITH 625 SX CMT
Liner: Size feet: 8/42.38

Well Type: SWD UIC Docket No: D17874.0 Date/Time to Plug: 05/16/2001 9:00 AM

Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (316) 275-7461

Proposed Plugging Method: PUMP 600 SX CMT & 400# HULLS FOR BOTTOM PLUG. GEL TO 1400'. PUMP CMT FROM 1400' TO SURFACE. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: SCOTT ALBERG
Date/Time Plugging Completed: 05/16/2001 10:30 AM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3750'. PERFS AT 3592-3608'. PUMP 1/2 BBL CMT DOWN 8 5/8" X 5 1/2" ANNULUS. PRESSURED TO 500#. PUMPED DOWN 5 1/2" CASING WITH 50 SX CMT WITH 300# HULLS MIXED IN - 15 SX GEL - 145 SX CMT. MAXIMUM PRESSURE 250 PSIG. SHUT IN PRESSURE 0 PSIG.

RECEIVED
KANSAS CORPORATION COMMISSION

INVOICED
DATE 5-30-01
NO. 2001061857

MAY 30 2001
5-30-01
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

MAY 24 2001

Form CP-2/3