

15-135-21073-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

11-12-75

Operator's Full Name Dane G, Hansen Trust

Complete Address Box 187, Logan, Kansas

Lease Name McFadden Well No. 4

Location C SE NW Sec. 34 Twp. 20 Rge. (E) (W) 22

County Ness Total Depth 4350'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor C & G Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 12 N Day 8 Month 11 Year 1975

The above well was plugged as follows:

RTD 4350' 8 5/8 csg set 415' cwc 200 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 550' thru drill pipe.

Heavy mud to 300' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 11/12/75

INV. NO. 2233-U