

15-135-21040-0000

~~KANSAS~~

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 24 1975  
4-24-75  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name O. A. Sutton  
Complete Address 800 Sutton Place, Wichita, Kansas  
Lease Name Dean Well No. 2  
Location C SW NE Sec. 33 Twp. 20 Rge. (E) (W) 22  
County Ness Total Depth 4361'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Gabbert-Jones Drlg.  
Address Wichita, Kansas License No.         
Operation Completed: Hour 8:20 A Day 20 Month 4 Year 1975

The above well was plugged as follows:

RTD 4361' 8 5/8 csg 457' cwc 300 sk. Plg. Mat. 60-40 poz cem. 2% gel  
Gunned pits, circulated heavy mud, set 50 sk cmt plug at 550' thru drill pipe/  
Heavy mud to 300' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set  
solid bridge & 10 sk cmt plug to base of cellar.  
        
        
        
      

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED  
DATE 4/29/75  
INV. NO. 1253-W