

15.135 20874-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JAN 8 1975
1-8-75
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name O. A. Sutton
Complete Address 800 Sutton Place, Wichita, Kansas 67202
Lease Name Baricklow Well No. 1
Location NE NE Sec. 33 Twp. 20 Rge. (E) (W) 22
County Ness Total Depth 4348' 4410
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Nicholos Casing Pulling
Address Box 373, Geneseo, Kansas 67444 License No. 711
Operation Completed: Hour 8P Day 4 Month 1 Year 1975

The above well was plugged as follows:

Total depth 4348' 8 5/8 csg set at 411' cwc 250 sk.

5 1/2 csg set at 4347' cw 150 sk cem.

Mixed & pumped 100 sk comm cem down 5 1/2 csg -top of cem. 3200'.

Cutoff & recovered 1695' of 5 1/2 csg.

Mixed & pumped down 8 5/8 csg (thru plug container) with 20 sk gel & water -

released plug & pumped 125 sk 60-40 poz cem. by HOWCO. PP 600 lbs. SIP 400 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 1/15/75
INV. NO. 046-W