

15-165-20033-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 5 1967
6-5-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mull Drilling Company Inc.,

Complete Address: 1625 Wichita Plaza Wichita, Kansas

Lease Name Maresch Well No. 1

Location SW NW Sec. 32 Twp. 19 Rge. 19 (E) (W) X

County Rush Total Depth 4290

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Vaughn Drilling Co.

Address: Box 825 Great Bend, Kansas License No.

Operation Completed: Hour 9 P Day 2 Month 6 Year 1967

The Above well was plugged as follows:

RTD 4290 8 5/8 csg set at 281' cwc

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 25 sc cem.

thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. J. Messing
Well Plugging Supervisor

DATE 6/6/67

INV. NO. 5340-W