



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
APR 21 1975
4-21-75
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Edmiston Oil Company
Complete Address 405 First Natl. Bank Bldg., Wichita, Kansas
Lease Name Maresch Well No. 1
Location 50' SE of C NW NW Sec. 29 Twp. 19 Rge. (E) (W) 19
County Rush Total Depth 4360'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Bergman Drlg.
Address Ellinwood, Kansas License No.
Operation Completed: Hour 4 A Day 19 Month 4 Year 1975

The above well was plugged as follows:

RTD 4360' 8 5/8 csg set 400' cwc 225 sk. Plg. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 50 sk cmt plug at 550' thru drill pipe.
Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set
solid bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo L. Massey
Well Plugging Supervisor

DVE 4/24/75
INV. NO. 1210-W